



| | |
|----|--|
| 01 | Red multi brickwork with natural mortar Brick Type: Terca Durham Claret Stock |
| 02 | Vertical format aluminium Cladding - Moonstone Blue |
| 03 | Horizontal format aluminium Cladding - Moonstone Blue |
| 04 | Smarts AllTherm PPC aluminium windows Finish: Anthracite Grey [RAL 7016] |
| 05 | PPC Aluminium Spandrel Panels in dark grey [RAL 7016] |
| 06 | PPC Aluminium Coping - RAL 7016 |
| 07 | PPC Aluminium Signage / Canopy - refer to separate details |
| 08 | Toughened glass balustrade in PPC M/S frame - RAL 7016 with SS handrail |
| 09 | Recessed brick panel to match main body brick |
| 10 | Glazed curtain walling system, with PPC aluminium finished mullion/transoms [RAL 7016] |
| 11 | Dark engineering brick to base of metal cladding |
| MJ | Movement Joints - please note horizontal joints to be 12-15mm - all to S/E details |

1. This drawing must be read in conjunction with all other scheme drawings.
2. All dimensions must be checked and verified on-site prior to construction.
3. Any discrepancies between co-ordinated information or given dimensions must be reported to the Architect immediately.
4. This drawing must not be scaled.
5. All materials subject to local authority approval

| | | |
|----------------|------------------------------|--|
| Job: | X1 - The Edge | |
| Client: | X1 Developments | |
| Drawing Title: | St. Vincent Street Elevation | |
| Date: | 4th November 2013 | |
| Drawing no: | 1052-111 | revision: L |
| Scale: | 1:100 @ A1 | |
| Drawn: | Jamie Thompson | |
| Revision | Date | Description |
| A | 14.11.13 | Window positions updated |
| B | 29.01.14 | bay windows added small window proportion amended vehicular access omitted and replaced with pedestrian access |
| C | 28.05.14 | Updated for contract drawings |
| D | 25.06.14 | Updated for construction grid added |
| E | 01.08.14 | Gridline 08 amended |
| F | 27.09.14 | Window labels added additional level information added key plan added |
| G | 15.10.14 | Movement joints indicated |
| H | 10.11.14 | Detail references added |
| I | 03.12.14 | Lowouries indicated to basement between gridlines 7 & 10 |
| J | 09.12.14 | window references updated as clouded |
| K | 11.02.15 | WB-06 sub station door updated |
| L | 18.04.15 | Windows updated to top hung material key updated vents added to gym area |

