

**BOUNDARY TYPE REFERENCES**

- E - existing
- N - new

This is then identified by material  
 C - Concrete, S - stone, B - brick, T - timber, SR - steel rail, SM - steel mesh, PV - post and wire

Interpret the code:  
 Brick Walls:  
 Existing of New & Height / Coating Type / Finishing or fence / Treatment  
 eg. NB6/C2/SR53 - = new brick wall 600mm high, sleep angle coping, steel rails 500mm high, no treatment

Timber fences:  
 Existing of New & Height / Type / Gravel Board / Treatment  
 eg. NT18/CB/G3 - = new timber fence 1800mm high, close boarded, gravel board, no treatment

Steel:  
 Existing of New Type & Height / Keel / Treatment  
 eg. NSR12/K1/ME - = new steel railings 1200mm high, flush pin keel, mesh existing

Timber Fences  
 CB - close boarded  
 P - palisade  
 T - trellis  
 CBP - close boarded slatted panel

HM - HI and miss  
 KR - knee rail  
 GB - gravel board

CP - close boarded slatted panel  
 C5 - Brick on edge.

**PIERS & CAPINGS**

- Brick pier (BP)
- 230mm Painted, see dwg DT(90)07
- 190mm Painted, see dwg DT(90)07
- High roll, see dwg DT(90)07
- Flat top, see dwg DT(90)07

Flush pin keel, see dwg DT(90)02 ref A  
 Upstand pin keel, see dwg DT(90)02 ref B  
 Half batter keel, see dwg DT(90)01  
 Drop keel, see dwg DT(90)01  
 Flag on edge.

Removal of existing brick  
 Bin Store structure.  
 This zone is to be agreed.

Structures/walls to be demolished!

**BOUNDARY TYPES**

Stone	Timber
Brick	Steel railings
Steel Mesh	Post and Wire
Concrete	Junction

Boundary Detail Drawings:  
 Stone Walls: DT(90)06, DT(90)07, DT(90)08, DT(90)09, DT(90)10, DT(90)13, DT(90)30, DT(90)37, DT(90)47, DT(90)62, DT(90)66, DT(90)71  
 Timber Fences: DT(90)19, DT(90)20, DT(90)21, DT(90)22, DT(90)23, DT(90)70  
 Steel Railings: DT(90)14, DT(90)15, DT(90)82

EXISTING GATES  
 Existing gate  
 Existing double gate

**NEW GATES**


G1	1200mm (h) 1000mm (w) steel gate, NBS: Q40/560B (see dwg DT(90)15)	G1	1200mm (h) 2000mm (w) steel gates, NBS: Q40/560H (see dwg DT(90)33)
G2	1200mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560C (see dwg DT(90)32)	G2	1500mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560I (see dwg DT(90)32)
G3	1200mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560E (see dwg DT(90)29)	G3	1800mm (h) 1500mm (w) (lh) timber gates, NBS: Q40/570F (see dwg DT(90)40)
G4	1500mm (h) 1000mm (w) steel gate, NBS: Q40/560C (see dwg DT(90)29)	G4	1000mm (h) 840mm (w) steel gate, NBS: Q40/560K (see dwg DT(90)50)
G5	1500mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560F (see dwg DT(90)29)	G5	1200mm (h) 2800mm (w) (lh) steel gates, NBS: Q40/560L (see dwg DT(90)38)
G6	1800mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560F (see dwg DT(90)29)	G6	1800mm (h) 1500mm (w) (lh) steel gates, NBS: Q40/560Q (see dwg DT(90)43)
G7	1200mm (h) 1000mm (w) steel gate, NBS: Q40/560C (see dwg DT(90)29)	G7	1200mm (h) 1000mm (w) steel gate, NBS: Q40/560M (see dwg DT(90)38)
G8	1300mm (h) 900mm (w) single steel gate, NBS: Q40/560N (see dwg DT(90)46)	G8	1300mm (h) 900mm (w) double steel gates, NBS: Q40/560O (see dwg DT(90)46)
G9	1000mm (h) 1500mm (w) (lh) double steel gates, NBS: Q40/560P (see dwg DT(90)49)	G9	1000mm (h) 1800mm (w) double steel gates, NBS: Q40/560R (see dwg DT(90)49)
G10	1000mm (h) 1000mm (w) timber gate, NBS: Q40/570M (see dwg DT(90)53)	G10	1000mm (h) 1000mm (w) timber gate, NBS: Q40/570L (see dwg DT(90)53)

**SURFACES**

WIP	Existing waste pipe	WIP	Existing water valve location.
SP	Existing soil pipe	GU	Existing gully
MH	Existing manhole cover	W	Existing water valve location.
gas2	Existing gas main	MH	Existing manhole cover
Gr	Existing gas valve location.	gas2	Existing gas main
CATV	Cable tv cover in footpath	Gr	Existing gas valve location.
TWB	Cable tv box on building, low level	CATV	Cable tv cover in footpath
NAD	New ACO drain	TWB	Cable tv box on building, low level
EDC	Ground Drainage Channel	NAD	New ACO drain
DP	Existing Downpipe	EDC	Ground Drainage Channel


**Notes:**

This drawing is to be read in conjunction with all other relevant drawings  
 Do not modify or dimension of the drawing  
 Use dimension only for purposes of the drawing  
 Name: S41 PL(90)825



The following external model files are included within the drawing:

Notes:  
 Foundations, structural elements and drainage systems subject to Engineers design and detailing. All existing stumps and tree pits to be removed and area to be made good and to match to existing surroundings NBS: D20/171. Unless, otherwise stated all new hard surfaces to be laid to existing drainage channels' guides.  
 Access:  
 Where there is a single low step to block entrance ways, the access path should, where practicable and ensuring gradients do not exceed 1:20, be graded out from top of step down to level of existing drainage slope and step access for all residents and visitors.  
 Existing paving to be retained to be treated with weed killer  
 Boundary treatments:  
 Ensure the top of new gates is level with the top of adjacent new railings.



<b>EXISTING</b>	Existing Paving	Existing Timber decking	Existing Gravel / Cobbles	Existing Asphalt/Tarmac	Existing Concrete Surface	Proposed Lit & Relay or Replace Existing Paving NBS: Q25/121 (50% unless otherwise stated on drawing) New Paving NBS: Q25/120 (see dwg DT(90)00)
<b>SOFT</b>	Existing Grassland	Existing Trees	Existing Specimen Shrub/Hedge	Existing Planting Bed	Existing Worn / Poor Quality / Heavily Overgrown Grasslands	Existing Bare Earth
<b>PROPOSED</b>	New Turf NBS: Q30/400	New Different Planting Beds. NBS: C31	Proposed Trees	Remove stumps and make good. NBS: D20/160D	Proposed Trees	Proposed Trees
<b>FURNITURE</b>	Existing steps to be graded out to form new ramp or existing ramp to be re-graded with new handrail.	Existing ramp	Existing concrete bollard to be removed.	Existing handrails	Existing washing line	Existing timber shed
<b>EXISTING</b>	Existing Greenhouse	Existing Greenhouse	Existing Greenhouse	Existing Greenhouse	Existing Greenhouse	Existing Greenhouse
<b>PROPOSED</b>	New steps and handrails.	Indicative location of wheeable bin	New concrete bollard.	New handrails.	New cycle stands.	New cycle stands.

**EXISTING BUILDING HEIGHTS**

One-storey residential blocks.	Two-storey residential blocks.	Three-storey residential blocks.	Four-storey residential blocks.
--------------------------------	--------------------------------	----------------------------------	---------------------------------

**PROPOSED SITE PLAN**  
 S41 QUARRY STREET Sheet 1 of 1

Job Number	5898	Drawing Original Date	06/01/2015	PAS T182 Status Code	
Scale/Alt	1:100	Purpose	PLANNING	Revision	C
Drawing Number	5898 S41 PL(90)825				

**LIH**  
 Landscape & Horticulture  
 Intelligent Infrastructure  
 www.lihgroup.com

**LIH**  
 LIVERPOOL MUTUAL HOMES ENVIRONMENTALS