



Proposed Front Elevation



Proposed Rear Elevation

- NOTES, GENERALLY**  
Carefully prop and take down existing stacks below roof level and rebuilt to match existing with stone capping over.
- Leadwork to newly formed stacks & stepped flashing to be Code 6 Lead
- Provide leadwork to rear elevation where existing factory units abutments, dressed into brickwork etc with Code 6.
- All rainwater goods (down spouts and hoppers) are to be replaced with cast iron by specialist suppliers.
- Where required, for areas of defective brickwork that are to be rebuilt for remedial purposes, the brickwork shall be salvaged brickwork to match existing. All rebuilding must be carried out using lime mortars to LCC Spec.
- Provide new sandstone heads and cills to new windows to match existing.