


Notes

ALL DISSIMILAR MATERIALS TO BE ISOLATED BY THE USE OF PVC ISOLATING TAPE.  
ALL SUPPORT MEMBERS ARE BY OTHERS UNLESS NOTED OTHERWISE.




FL30(A) & (B) 1.6mm THICK GALV TOP HATS TH (A) TO BE RADIUS AS NOTED & SECURED HORIZONTALLY AT 1260mm VERTICAL CENTRES.  
TH (B) TO BE INSTALLED VERTICALLY AT 660mm CENTRES. BOTH SECURED USING SD3 5.5x25mm SCREWS AT 400 CENTRES.

35/40mm THICK PIR INSULATION BOARD 600mm WIDE INSTALLED VERTICALLY BETWEEN VERTICAL TOP HATS.

40mm THICK PIR INSULATION BOARD INSTALLED HORIZONTALLY & SPLIT AT 400mm CENTRES TO CREATE FACET

SFS FRAMEWORK IS SUPPLIED & INSTILLED BY OTHERS.



FL05 0.7mm THICK STEEL DRIP FLASHING. FINISH TO MATCH PANELS & SECURED USING FLAT HEAD ST STEEL SCREWS AT STUD CENTRES.


FL06 70x70x1.6mm THICK GALV CLEADER SECURED USING FLAT HEAD SCREWS AT STUD CENTRES.

CAVITY FILLED USING FR RATED CANISTER APPLIED INSULATION

+20,135 SSL



INSULATED ROOF GUTTER COMPRISING OF 0.7mm WHITE LINER, 50mm THK PIR INSULATION & 1.2mm THICK MEMBRANE LINED TOP LAYER. ALL SECURED USING SD3-T15 5.5x25mm SCREWS.



FL10 1.5mm THICK CORTEN COPING FINISH TP MATCH PANELS & SECURED USING SDP3-T16 5.5x32 SCREWS AT 400 CENTRES.

FL09 1.6mm THICK GALV ZED SECURED USING FLAT HEAD SCREWS AT TOP HAT CENTRES.

SIDE EXIT OUTLET TO GUTTER TO DRAIN ONTO ROOF BELOW - ROUTE IS TO BE DETERMINED.

DETAILS OF EXISTING COPING STONE IS TO BE SITE SURVEYED IN ORDER TO COMPLETE THIS DETAIL.



Hilbre Court Business Centre  
Corporation Road, Birkenhead  
Wirral CH41 3NG

Tel: 0151 649 0001  
Fax: 0151 647 7088

Client  
NU CONSTRUCTION Ltd.

Contract Title  
CHANCERY HOUSE  
LIVERPOOL

Drawing Title  
ROOF POD GUTTER DETAIL  
OVER EXISTING BUILDING  
(BUILT UP SYSTEM)

Rev	Date	Revisions
-		

Drawn	WBW	Date	MAR 2016
Checked		Scale	1:5 @ A3