Key

Existing

- Trees (with new understorey planting)
- 5m buffer from edge of woodland areas
- Application boundary
- Retained grassland

Proposed Hard Landscape Elements

- Resin bound surfacing with sett edging
- Self binding gravel path with timber edging
- Entrance piers
- Estate railings
- Bench
- Bin/Dog Bin

Proposed Soft Landscape Elements

- Native and Wildlife Friendly Trees
- Species-rich Native Broad Hedgerows (1.8m wide and 1.8m high providing wildlife corridors along edges of open space)
- Species-rich Native Broad Hedgerows (1.2m wide and 1.2m high providing wildlife corridors along edges of open space)
- Woodland Edge Scrub Planting inter-planted into Woodland Edge Grassland
- Woodland Edge Grassland
- Neutral Grassland (with a 1m mown grass edge to either side of footpaths)
- Mown Grass
- Front Gardens (Amenity Grass)
- Rear Gardens (Amenity Grass)
- Ornamental Hedgerow
- Ornamental Planting
- Bulb Planting
- Amphibian refuge

Reproduced by permission of Ordnance Survey on behalf of Her Majesty's Stationery Office.

© Crown Copyright and database right 2014. All rights reserved. Licence Number 100022432.

Rev	Description	Drawn	Approved	Date
K	Amendments to Phase 3 layout	SW	CH	02/12/2019
J	Amendments to suit new layout	SW	CH	27/09/2019
I	New layout received	SW	CH	03/05/2019
H	Amendment to hedgerows/trees/seeding	SW	JTS	24/09/2018
G	Amendment to existing vegetation at access point	AL	SW	10/09/2018
F	Amendments to access	AL	SW	10/09/2018
E	Amendments for planting design	AL	SW	31/08/2018
D	Amendment to Layout	SO	JTS	06/08/2018
C	Amendment to Layout	SO	JTS	19/07/2018
B	Amendment to Hedgerow	MB	JTS	27/04/2018
A	Amendment to Layout	MB	JTS	27/04/2018

TEP | THE ENVIRONMENT PARTNERSHIP

Genesis Centre, Birchwood Science Park, Warrington WA3 7BH
Tel 01925 844004 e-mail tep@tep.uk.com www.tep.uk.com

Project
Woolton Road, Allerton

Title
Landscape Masterplan

Drawing Number
D4729.007K

Scale	Date
1:1000 @ A1	09/04/2018

Drawn	Checked	Approved
MB	JTS	JTS