



Allow to replace say 1m run of backing framing in treated sw.

Replace missing in sw inc moulting.

Replace in t+g sw boarding.

Replace in t+g sw boarding.

Mild steel guard bars with metal frame bolted into brickwork, with fly mesh.

Firm fix existing timber pilaster.

Laminated glass upper panels, internal beading.

Glass fanlight.

Polyester powder coated aluminium fascia in painted sw frame, with fret cut letters with perspex covers, back lit.

Cut out + replace in sw in matching profile.

Replace missing in sw to match adjacent.

New moulded se Mullions and transoms.

Upper glazed panels in separate sw subframe set behind main frame.

22mm wbp ply, with planted on 13mm ply panel.

22mm wbp ply, with planted on 13mm ply panel.

Traditional timber panelled door, 22mm ply panels with moulded panel beads.

Make good render and repaint.

Renew in sw.

Repaint render.

Traditional timber panelled door, 22mm ply lower panels with moulded panel beads.

# NEW GATES

Traditional timber panelled door, 22mm ply panels with moulded panel beads.

Redecorate all new and existing timber and repaint render.



ARCHITECTURE INTERIOR DESIGN CONSERVATION

DENOVO DESIGN LTD  
89 WOOD STREET, LIVERPOOL, L1 4NU  
tel: (0151) 708 4999 fax: (0151) 708 5335  
e-mail: post@denovodesign.ltd.uk  
www.denovodesign.ltd.uk

44 Berry Street Liverpool for Miss A. Nasuh

Rev A : 7 Sept 15 : de : issued for planning

## FRONT ELEVATION AS PROPOSED

Drawn: DE July 15 Checked: 1:50 @A3

DN301.C.21 A