



New lead gutter + covering
to cornice + blocking course
- see dwg C33.

Strap existing cornice to
wall below.
Carefully cut out spalled stone
and indent new matching colour
natural stone, moulded to match.

Repoint.

3 no new sash
windows.

repair 3 no existing
sash windows.

New cast iron rwp
and hopper.
Firm fix timber cornice,
renew lead covering
and flashing.

Replace missing panel
in timber inc moulding.

Firm fix existing
timber pilaster.

New door, frame +
grill overpanel -
see dwg. C21.

New shopfront +
timber doors+ frames
- see dwg. C21+22.

HEALTH + SAFETY;
Proximity of public.
Provide toe boards + barriers,
to ensure that objects do not
fall from scaffold. Hoard off
works as necessary. Remove
ladders at end of working day.

ELEVATION TO BERRY ST



DENOVO DESIGN LTD
89 WOOD STREET, LIVERPOOL, L1 4NU
tel: (0151) 708 4999 fax: (0151) 708 5335
e-mail: post@denovodesign.ltd.uk
www.denovodesign.ltd.uk

Rev A : 7 Sept 15 : de : issued for planning

44 Berry Street Liverpool for Miss A. Nasuh

REAR ELEVATION AS PROPOSED

Drawn:
DE July 15

Checked:
.

1:50 @A3

DN301.P.16

A