



THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY FROM THE OWNER.

**NOTE:**

- Do not scale from this drawing. Always work to noted dimensions.
- All dimensions are in millimetres unless otherwise stated.
- All setting out, levels and dimensions to be agreed on site.
- The dimensions of all materials must be checked on site before being laid out.
- This drawing must be read with the relevant specification clauses and detail drawings.
- Order of construction and setting out to be agreed on site.

- KEY TEMPORARY WORKS**
- Temporary Food & Beverage Unit (A&B)**
- Converted Large 40ft & Medium 20ft Shipping - requiring water, waste & power supply
- Container Type A - (Under-storey)**
- size: 12192(L) x 2438(W) x 2500(H)mm
  - quantity: 1No.
- Container Type B - (Upper-Storey)**
- size: 12192(L) x 2438(W) x 2900(H)mm
  - quantity: 1No.
- Container Type C (Under-Storey)**
- size: 6096(L) x 2438(W) x 2500(H)mm
  - quantity: 7No.
- Container Type D (Upper-Storey)**
- size: 6096(L) x 2438(W) x 2500(H)mm
  - quantity: 2No.
- Stepped approach to upper containers** with low handrails and tactile paving
- Gated access to rear of containers**
- Refer to information produced by White Circle for additional information on the temporary containers

- Rapid Retail Unit**
- Size: 5000(L) x 2400(W) x 2700(H) mm
  - Quantity - 4No.
- Temporary Trailer Stage**
- 2.44m High Hoarding**
- Exterior grade plywood
  - Refer to detail on drawing GA.021
- Concrete Jersey Barriers** (Temporary Counter-Terrorism Measure)
- Interlocking Modular Design
  - Size: 2500(L)x610(W)x810(H)
  - 1.7m Spacing as shown
  - Quantity: 26no. shown
- CYCLE STANDS - 8no.**
- Standard Sheffield Hoop in stainless steel. Roof fixed. To be agreed with Engineer.
- Planning Application Boundary**
- LFC Ownership Boundary**
- Potential Temporary Drainage**
- Subject To Engineer's Design + Review
- Proposed lighting Column - A1**
- 15m pole
  - 4no. optics @ 13m
  - 3no. shown
- Proposed lighting Column - B1**
- 12m pole
  - 6no. optics
  - 4no. shown
- Retained bitumen macadam surface**
- Retained concrete surface**
- Proposed bitumen macadam surface**

5	19.05.16	Minor Amendments	JV	GB
4	18.05.16	Minor Amendments	JV	GB
3	17.05.16	Issued for planning	JV	GB
2	26.04.16	Issued for planning	SF	GB
1	08.04.16	Issued for comment	JV	LH
Issue	Date	Status	Drawn	Apprvd.

**Planit Intelligent Environments LLP**

E: info@planit-ie.com W: planit-ie.com

**MANCHESTER** 2 Back Grafton St. Altrincham WA14 1DY T: 0161 928 9281

**LONDON** 18 Bowling Green Lane EC1R 0BW T: 0207 253 5678

Client Liverpool Football Club

Project New Anfield

Drg Title Anfield Plaza Temporary Solution Final Hardworks

Created on 08/04/16 Created by JV Approved by GB

Scale 1:250 Size A1 Status Planning

Drg No. PL1312.4.GA.011 Issue 05