

This drawing is issued in confidence. It must not be copied, used or disclosed to third parties without the express permission of NJSR. It remains NJSR's property and must be returned on request.
It is the contractor's responsibility to report any inconsistencies on this drawing, or between drawings, to NJSR and to request clarification and instruction before proceeding. Do not scale from this drawing. All dimensions to be checked on site prior to construction or manufacture

REVISION	DATE	DESCRIPTION	DRAWN	CHECKED
A	10.10.13	Updated to client comments	as	
B	04.10.13	Point 6,10,13,14,20,21,25 & 27 updated to client comments	as	
C	01.07.14	Demo & Construction Updates	oh	db
D	16.07.14	Updated following site meeting 08/07/14 and pop-up added. Also updated to client meeting 14/07/14.	rb	db
E	21/07/14	Updated entrance and pop-up dimensions added	rb	db

SCOPE OF WORKS LEGEND

Requirements of Landlord

- External roller shutter into communal corridor
- Driver access door into communal corridor - LIDL CONFIRMED NO LONGER REQUIRED
- Blend public highway to suit level delivery access into communal corridor.
- Remove raised slab to provide level access from communal corridor into unit.
- Ensure communal corridor walls and columns adequately protected to withstand impact from stock movement. Metal plates and angles.
- Doors to stockroom to be fit for purpose of stock movement and emergency escape. To be adequately protected.
- Doors to stock from communal corridor to have Lidl specification ironmongery.
- Ensure doors to communal corridor are 2.3m minimum height, from Lidl unit to communal loading bay.
- Provide overhead sectional door to warehouse. To achieve compartment specification. Specification to be agreed with Lidl.
- REMOVED
- Remove redundant escalator beams and make good cladding to columns
- Generally, all ceilings / soffits to be clear of debris, and redundant or loose fittings.
- De-Clad 5 number columns in proposed warehouse. To be fire rated appropriately. Subject to Local Authority approval.
- De-Clad 4 number columns in proposed Staff facilities. To be fire rated appropriately. Subject to Local Authority approval.
- Construct new shaftwall compartment wall. Landlord has proposed future demolition adjacent so specification to be robust enough to withstand / maintain compartmentation.
- Reform Stair 1 lobby as compartment to suit Lidl arrangement and escape strategy.
- Provide 2 number double doors to Lidl standard with ironmongery
- Provide 1 number door to Lidl standard with ironmongery.
- Remove mezzanine & associated structure. Remedial works to columns, walls and floors.
- Construct new 'retaining wall' to lowered window backs. Landlord to construct at Lidl's expense on an open book basis.
- Infill lowered window backs with flooring suitable for loadings of retail unit, to Lidl performance requirements. Landlord to construct at Lidl's expense on an open book basis.
- De-clad entrance columns.
- Re-clad 7 number columns with stone fluting & detailing.
- Provide new entrance auto-doors & glazing. Number & spec TBC.
- Remove raised window floors. Landlord to construct at Lidl's expense on an open book basis.
- Landlord to provide details of glazed wall to escalator to allow co-ordination with Lidl fixtures and ceiling.
- New ramps/change in level to be provided within communal corridor to suit level delivery access into Stockroom.
- Steps to communal loading bay relocated
- Provide area of plant deck for Lidl, and access routes from Lidl unit.
- Provide approx 11 number drainage popups to locations within Lidl unit. Position to be agreed.
- Provide Incoming services to locations agreed with Lidl on back wall. Position to be agreed.
- Provide area of reducing flooring & drainage for sluice. Position to be agreed.
- Landlords and other tenant's services to be boxed in with leak detection back to Landlord's BMS or similar.
- Front Entrance; remove 2 no. redundant aluminium signage boxes & make good stone/window.
- Front Entrance; Clean stone to signage zones prepared to receive Lidl signage.
- Repair or replace damaged sections of column cladding.

Lidl Agreements

- Existing terrazzo floor. Lidl to seal screed & lay new floor. N.B. Possible no flooring warranty dependant on contractor.
- Already constructed stud partition compartment walls; Lidl to provide impact protection though low level bump rail and
- Lidl make good minor flooring works prior to flooring works.
- Lidl to blend flooring to entrance level to accommodate standard floor finish. Landlord to confirm floor build up and what depth can be removed.
- Lidl to clad interior face of shopfront piers.
- Lidl to use portable freezers instead of forming recess into floor.
- Box-out SVP to raised window section

Consents

- Landlord to submit planning application, including listed building consent for shell works listed above.
- NJSR & Lidl to provide drawings and supplementary statements to landlord for inclusion of submission.
- Landlord to obtain building regulations approval for shell works.
- NJSR & Lidl to obtain building regulations approval for fit-out.
- NJSR & Lidl to obtain advertisement consent.
- Landlord to ensure all ceiling suspension agreed with local authority and conservation as part of planning application.

STATUS:

PRELIMINARY FOR COMMENT



SOUTHPORT | t: 01704 531 252 | f: 01704 532 833 | e: southport@njsr.co.uk
MANCHESTER | t: 0161 873 8770 | f: 0161 873 8771 | e: manchester@njsr.co.uk
WWW.NJSR.CO.UK WWW.NJSRPROJECTSERVICES.CO.UK
Client

Lidl UK GmbH

Project

Project Name Lewis's, Ranelagh St,
LIVERPOOL

Title

Shell Construction

Scale	Date	Drawn	Checked
1 : 200	21/07/14	rb	db
Contract	Dwg. No.	Rev	
1372.005	S002	E	